Lumbini Province Government

Ministry of Physical Infrstructure Development

Transport Infrastructure Directorate

Road Infrastructure Development Office

Tansen,Palpa

Bill of Quantity (BOQ)

Name of Road:- Upgrading of Deurali-Kaule-Lumbas-Fek Gramin Sadak, Ribdikot-08, Palpa & Upgrading of Byarikot Chowk Palung Mukhya Chur Gramin Sadak

CONTRACT ID:RIDO-PAL-W-NCB-20-2083/084

Pay Item No.	Dscription	Unit	Quantity	Rate in Figure	Rate in Words	Amount	Remarks
1.0	Insurance of works, plants, equipment, construction materials and manpower all complete as per Contract. (GCC13)	PS	1.00	59000.00	Rs. Fifty Nine Thousand Only	59000.00	
2.0	Provisional sum for relocation of services and repairing for existing infrastructure (Telephone wire, Electric pole & wires, water supply pipes, Hume pipes,kulos, Temple, Foot staircase, Foot trail etc), reconstruction of public infrastructure , Environmental mitigation, Social works, supply of Engineer's facilities, camp/laboratory equipments etc. including other relevant unforseen work items as necessited and instructed by engineer.	PS	1.00	18500.00	Rs. Eighteen Thousand Five Hundred Only	18500.00	
3.0	Roadway excavation in all types of soil as per Drawing and Technical Specification including removal of stumps and other deleterous matter, all lift and leads as per Drawing and Instruction of the Engineer. (Mechanical Means)(Sp 905&9.1.I.B)	Cum	189.00				
4.0	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)(Sp 907&9.4.I.B.i)	Cum	632.77				
5.0	Haulage (Transportation) Charge for Ecxavated soil on safe site.	Cum	300.94				
6.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(Sp 1000&10.08)	Cum	294.45				
7.0	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications(Sp 2000&20.02.A)	Cum	3.00				
8.0	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications(Sp 2000&20.02.B)	Cum	280.77				
9.0	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)(SP 2421&24.21.A.I)	Cum	61.98				
10.0	Providing and Laying RCC 300mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications(Sp 701&7.2A)	Rm	5.00				
11.0	Supply, place and maintain standard size 1.0 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper [110]	Nos	2.00				
					Total without PS		
					VAT @ 13%		
					Total With Vat &PS		

In words

Name of Contractor:-

Address:-

Seal:-

Authorised Signature