Lumbini Provience Government

Ministry of Physical Infrstructure Development

Transport Infrastructure Directorate

Road Infrastructure Development Office

Tansen,Palpa

Bill of Quantity (BOQ)

Name of Road:-Upgrading Of Deurali Kamere Bithuwa Chandisthan Motorbato Bagnaskali-07

CONTRACT ID:RIDO-PAL-W-NCB-24-2083/084

Pay Item No.	Dscription	Unit	Quantity	Rate in Figure	Rate in Words	Amount	Remarks
1.0	Insurance of works, plants, equipment, construction materials and manpower all complete as per Contract. (GCC13)	Ps	1.00	25000.00	Rs. Twenty Five Thousand Only	25000.00	
2.0	Provisional sum for relocation of services and repairing for existing infrastructure (Telephone wire, Electric pole & wires, water supply pipes, Hume pipes,kulos, Temple, Foot staircase, Foot trail etc), reconstruction of public infrastructure , Environmental mitigation, Social works, supply of Engineer's facilities, camp/laboratory equipments etc. including other relevant unforseen work items as necessited and instructed by engineer	Ps	1.00	12000.00	Rs. Twelve Thousand Only	12000.00	
3.0	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means) (90% Mechanical & 10% Manual) (As per 9.4.I.A.i & 9.4.I.B.i, SS 907)	Cum	248.09				
4.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (As per 10.08, SS 1000)	Cum	119.38				
5.0	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications. (As per 20.02.A, SS 2000)	Cum	8.37				
6.0	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications(Sp 2000&20.02.C)	Cum	96.06				
7.0	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means) (As per 24.21.A.I, SS 2421)	Cum	28.69				
8.0	Providing mechanically woven double twisted crates / mattress including rolling, cutting and with lacing wire and binding wire Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 2.7 mm, selvage wire 3.4 mm, lacing wire 2.2 mm, assembling, placing in position including stretching; forming compartments; tying the sides and diaphragms with binding wire in each mesh; tying with bracing wires and tie wires; and tying down the lid with providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete.	Cum	62.50				
9.0	Supply, place and maintain standard size 1.0 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper [110]	Nos	1.00				
					Total without PS		
					VAT @ 13%		
					Total With Vat &PS		

In words

Name of Contractor:-

Address:-

Seal:-

Authorised Signature