Lumbini Province Government

Ministry of Physical Infrstructure Development

Transport Infrastructure Directorate

Road Infrastructure Development Office

Tansen,Palpa

Bill of Quantity (BOQ)



Name of Road : Upgrading of Deurali Kuwa Hungighat Sadak Rambha 1 Palpa

CONTRACT ID:RIDO-PAL-W-NCB-28-2083/084

Pay Item No.	Dscription	Unit	Quantity	Rate in Figure	Rate in Words	Amount	Remarks
1.0	Insurance of works, plants, equipment, construction materials and manpower all complete as per Contract. (GCC13)	Ps	1.00	20000.00	Rs. Twenty Thousand Only	20000.00	
2.0	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means) (90% Mechanical & 10% Manual) (As per 9.4.I.A.i & 9.4.I.B.i, SS 907)	Cum	141.05				
3.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (As per 10.08, SS 1000)	Cum	60.45				
4.0	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications(Sp 2000&20.01)	Cum	20.15				
5.0	Providing and laying of RCC (Grade M 25) in foundation complete as per Drawing and Technical Specifications. (As per 20.02.E, SS 2000)	Cum	80.60				
6.0	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (As per 20.5, SS 2014)	Mt	3.297				
7.0	Supply, place and maintain standard size 1.0 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper .[110]	Nos	1.00				
					Total without PS		
					VAT @ 13%		
					Total With Vat &PS		

In words

Name of Contractor:-

Address:-

Seal:-

Authorised Signature