Lumbini Province Government

Ministry of Physical Infrstructure Development

Transport Infrastructure Directorate

Road Infrastructure Development Office

Tansen,Palpa

Bill of Quantity (BOQ)

Name of Road : Upgrading of Dhunganabesi Kyangrung Admara Jhirbash Khadar Dundanda Muralikhola Hupsekot Sadak, Nisdi

CONTRACT ID:RIDO-PAL-W-NCB-29-2083/084

Pay Item No.	Dscription	Unit	Quantity	Rate in Figure	Rate in Words	Amount	Remarks
1.0	Insurance of works, plants, equipment, construction materials and manpower all complete as per Contract. (GCC13)	Ps	1.00	25000.00	Rs. Twenty Five Thousand Only	25000.00	
2.0	Roadway and drain excavation in all type of soil and rock material including disposal of excavated material at approved environmentally safe tipping sites. (As per 9.1.I.B,II.B&IV.A, SS 905)	Cum	37.50				
3.0	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means) (90% Mechanical & 10% Manual) (As per 9.4.I.A.i & 9.4.I.B.i, SS 907)	Cum	280.81				
4.0	Haulage (Transportation) Charge for Excavation soil on safe site.	Cum	96.95				
5.0	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (As per 10.08, SS 1000)	Cum	133.97				
6.0	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications. (As per 20.02.A, SS 2000)	Cum	7.05				
7.0	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications. (As per 20.02.B, SS 2000)	Cum	118.90				
8.0	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means) (As per 24.21.A.I, SS 2421)	Cum	12.00				
9.0	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications. (As per 26.3.B, SS 2602,26.3,26.7)	Cum	6.00				
10.0	Providing and Laying RCC 450mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications. (As per 7.2B, SS 701)	Rm	5.00				
11.0	Supply and place standard size sign board for contract information.	Nos	1.00				
					Total without PS		
					VAT @ 13%		
					Total With Vat &PS		

In words

Name of Contractor:-

Address:-

Seal:-

Authorised Signature